

Exhibit A
Description of Project
Resolution 2008-08

Detention Pond Retrofits
Rayne Road and Venice Avenue Ponds

This project consists of the retrofitting of two existing detention ponds from dry to wet basins to facilitate the removal of suspended solids prior to discharge. In addition to the excavation of the ponds, pedestrian trails will be constructed within the basins, native trees, shrubs and plugs will be planted and benches, trash receptacles and interpretive signage will be installed. A pedestrian bridge will be constructed at the Rayne Road pond.

Exhibit B
Project Budget
Resolution 2008-08

Detention Pond Retrofits
Rayne Road and Venice Avenue Ponds

Construction bid	= \$ 731,346.40
Contingencies	= \$ 40,653.60
Engineering, Legal & Administrative	= \$ 155,000.00
Additional Site Amenities	= \$ <u>18,000.00</u>
Total Project Cost	= \$ 945,000.00