

RESOLUTION 2008-71

8-29-08

**RESOLUTION BY THE STORM AND WASTEWATER COMMITTEE
AUTHORIZING CERTAIN DRAINAGE IMPROVEMENTS AT THE
STURTEVANT DEPOT**

WHEREAS, there is a need to construct certain storm water and drainage improvements at the Sturtevant Depot; and

WHEREAS, at this time the Village would like to proceed with said improvements at a cost not to exceed \$12,000.00 ; and

NOW THEREFORE, the Village Board of the Village of Sturtevant, Racine County, Wisconsin does hereby resolve:

1. That the soliciting of proposals and awarding of a contract to a vendor to do the work described in Exhibit A which is attached hereto and incorporated herein is authorized and approved and the Village President and the Village Clerk are authorized to sign any agreements or other documents necessary to carry out the intent of this resolution.
2. That the funds for said contract and said project are to be taken from account number: 203-51300-210.
3. That the construction costs are estimated to be \$9,400 and the total costs for the project shall not exceed \$12,000.00 which includes engineering, legal and administration and contingencies.

Adopted by the Village Board of the Village of Sturtevant, Racine County, Wisconsin, this 2nd day of September, 2008.

Village of Sturtevant

By _____
Steven Jansen, President

Attest _____
Mary Hanstad, Village Clerk

EXHIBIT A
RESOLUTION 2008-71

Depot Parking Area Drainage
Village of Sturtevant
Racine County, Wisconsin
Project No. R07-0019-032

The Depot Parking Area Drainage project in the Village of Sturtevant consists of constructing storm sewer at the southwest corner of the Depot parking lot. A catch basin will be placed within the radius of an existing corner within the East Exploration Court right-of-way southwest of the Depot property. Curb and gutter will need to be replaced since it will be damaged due to the underground storm sewer construction and to facilitate drainage to the new catch basin. 12 inch reinforced concrete pipe will extend east 50 feet to the existing island of the Depot and connect to an existing catch basin. 12 inch storm sewer will also be extended from an existing catch basin located 190 feet north of the previously mentioned storm sewer and tie into a new catch basin at the north end of the existing curb and gutter. Inlet protection is required for erosion control and lawn restoration and pavement replacement is required to restore the damage due to construction.