

RESOLUTION 2009-23

4-2-09

RESOLUTION BY THE ECONOMIC DEVELOPMENT AND REDEVELOPMENT COMMITTEE AUTHORIZING PRELIMINARY DESIGN WORK IN REGARD TO AN EAST ACCESS TO THE STURTEVANT DEPOT

WHEREAS, the Village of Sturtevant constructed the Sturtevant Depot and has leased it to Amtrak as an Amtrak train stop; and

WHEREAS, the original construction did not include an access from the east from Wisconsin Street to the Depot although some preliminary designs provided for this access; and

WHEREAS, the construction of a train depot and the construction of pedestrian paths are included in the existing TID plan and the Board of Trustees deems the construction of an east access to the Sturtevant Depot to be appropriate and beneficial to the TID.

NOW THEREFORE, the Village Board of the Village of Sturtevant, Racine County, Wisconsin does hereby resolve:

1. That the Village Administrator is authorized to proceed with preliminary design work and refined cost estimates in regard to the construction of an east access from Wisconsin Street to the Sturtevant Depot
2. That the project is generally described in Exhibit A which is attached hereto and incorporated herein.
3. That it is anticipated that the funds for this construction project, if approved by the Sturtevant CDA and the Village Board, shall be funds generated by the TID.
4. That the preliminary estimated total costs for said improvements is \$95,000.

Adopted by the Village Board of the Village of Sturtevant, Racine County, Wisconsin, this 8th day of April, 2009.

Village of Sturtevant

By _____
Steven Jansen, President

Attest _____
Mary Hanstad, Village Clerk

Exhibit A

Construction Cost Estimate (Preliminary)

Project Name: TID East Depot Tower Pedestrian Access
Client: Village of Sturtevant

Project No. R09-0019-101
Date: 3/16/2009
Rev 3/17/2009

No.	Qty	Units	Item	Unit Price	Total
Section 1 - Wisconsin Street to Tower					
1	1200	CY	Grading/Common Excavation	\$10.00	12,000
2	250	Ton	Base Aggregate Dense (6" thick)	\$14.00	3,500
3	120	Ton	E-0.3 Asphaltic Concrete (3" thick)	\$70.00	8,400
4	505	Lin. Ft	Handrail	\$10.00	5,050
5	1240	Sq. Ft.	Retaining Wall	\$20.00	24,800
6	2	Each	Removable Bollards	\$300.00	600
7	20	Lin. Ft	Remove Fence	\$10.00	200
8	185	Lin. Ft	Chain Link Fence	\$32.00	5,920
9	1	Each	Detectable Warning Field	\$200.00	200
10	1100	Sq. Yd.	Erosion Mat	\$4.00	4,400
11	1100	Sq. Yd.	Lawn Restoration	\$2.00	2,200
12	80	Lin. Ft	Guard Rail	\$30.00	2,400
13	2	Each	Bike Rack	\$1,500.00	3,000
14	2	Each	Sign	\$50.00	100
					<hr/>
					Total \$72,770
					Contingencies \$11,330
					Eng., Legal & Administrative \$10,900
					<hr/>
					Total Project Cost \$95,000

REVISION/PLOT DATE _____



EXHIBIT – EAST DEPOT TOWER PEDESTRIAN ACCESS

R09-0019-101

CRISPELL-SNYDER, INC.
PROFESSIONAL CONSULTANTS
Lake Geneva (920) 338-5620 Madison (608) 264-6277 Milwaukee Regional (414) 225-4000
Racine (262) 554-4530 Fox Valley (920) 752-4620

LOCATION: **VILLAGE OF STURTEVANT**

RACINE COUNTY, WISCONSIN

SCALE: **1" = 100'**

DATE: **MARCH, 2009**

DRAWN BY: **C. ELVIN**